MORSES CREEK

NEW BIKE TRACK PROPOSED TO BE LOCATED IN THIS AREA OF APPROX 4,500m2 . FINAL LOCATION TO BE CONFIRMED IN CONSULTATION WITH WINNING TENDERER AND COMMUNITY.

EQUESTRIAN ENCLOSURE

PROPOSED NEW BMX FACILITY

NEWLY CONSTRUCTED "HOT WHEELS" GREEN TRAIL

EXISTING PUMP TRACK

TENNIS COURTS

TENNIS COURT

182 m

AREA "A"

AREA "A" TO BE LEVELLED FLAT AND SEEDED

MYSTIC PARK SHELTER UNDER CONSTRUCTION & PROPOSED FOOTPATH IN BLUE

NEW WATERWAY DRAIN AND STORMWATER RECEIVING BASIN PLANTED WITH GROUND COVERS. OUTLET TO MORSES CREEK

PRIMARY OUTLET FROM RECEIVING BASIN DISCHARGING TO MORSES CREEK

NEW FENCING AND GATES TO DELINEATE TEMPORARY PARKING AREA

SECONDARY OUTLET FROM RECEIVING BASIN

PARKING AREA TO BE RETAINED

AREA "B"

27 m

CORONATION AVENUE

NEW 220m VEGETATED DRAINAGE SWALE TO CONNECT MYSTIC BASIN CREEK AND SUBDIVISION STORMWATER FLOWS INTO MORSES CREEK

NEW RECEIVING BASIN FOR STORMWATER FLOWS FROM MYSTIC BASIN CREEK

TREES CIRCLED IN BLUE TO REMAIN. ALL OTHER TREES IN AREA A & B TO BE REMOVED

MYSTIC LANE

EXISTING TWIN CELL 375 RCP UNDER ROADWAY

NEW FENCING TO DELINIATE PARKING AREA

NEW FENCING TO DELINIATE PARKING AREA

0 60 90 120 m

Tim Shilling | 12p Consulting | Albury NSW | m 0448 647 294 | e tim@12p.consulting | w 12p.consulting

PROJECT OVERVIEW FOR CONSULTATION

12p Consulting
Civil & Technical Project Management

ALPINE SHIRE COUNCIL

ALPINE EVENTS PARK | ALPINE SHIRE COUNCIL

REVISIONS

	MM/DD/YY	REMARKS
1	21/02/2020	LOAD SURVEY DATA AND AERIAL IMAGERY
2	24/02/2020	ADD LONG SECTIONS AND DRAINAGE/EARTHWORKS DETAILS
3	28/04/2020	REVISE SWALE DRAIN LOCATION
4	06/05/2020	UPDATE SWALE OUTLET TO NECMA REQUIREMENTS. REDUCE RCBC CROSSING WIDTH
5		
6		

C
02